Navigating Precision with Network Controls for Construction Continuity

AUTHORS:

Ernest Obiri-Yeboah, Paa Kwesi Ezanator Akuffo Owusu-Ensaw, Anthony Wordi, Joseph Owusu-Awuah, Portia Gyemfah Addo and Samuel Botchway(Ghana)









Your World, Our World: **Resilient Environment** and Sustainable Resource Management for All

CURRENT STAGE OF CONSTRUCTION

















Your World, Our World: Resilient Environment and Sustainable Resource Management for All

CONSTRUCTION PHASE I IMAGES





CONCENTRATOR AREA













HOW DID WE ACHIEVE THIS?

- **TRAVERSING:**
- Two main base line controls were used for the traversing: GBCT 06 and GBM 07 from these other 22 benchmarks were established around the construction site.
- Surpac least squares adjustment software was used for controls adjustment.
- Further transformation by Trimble business center of the controls and existing structures.
- New controls derived for construction continuity were tested and used through out construction.
- Close loop leveling traverse was also done for elevation purposes.













Your World, Our World: Resilient Environment and Sustainable Resource Management for All

TRAVERSE NETWORK DIAGRAM

















FIG Working Week 2024 19-24 May

Accra, Ghana

Your World, Our World: **Resilient Environment** and Sustainable Resource Management

DESIGN VRS ASBUILT DATA AFTER ADJUSTMENT TRANSFORMATION RESULTS

			DESIGN		ASBUILT			DIFFERENCE		
SL.NO	NAME		NORTHI NG	ELEVATIO N			ELEVATIO N		NORTHI NG	ELEVATIO N
1	THF-1	296.603	318.250	480.750	296.617	318.243	480.742	-0.014	0.007	0.008
2	THF-2	296.603	328.950	480.750	296.623	328.943	480.741	-0.020	0.007	0.009
		1.00		7.9h						
3	THF-3	307.603	328.950	480.750	307.616	328.947	480.740	-0.013	0.003	0.010
4	THF-4	307.603	318.250	480.750	307.621	318.256	480.742	-0.018	-0.006	0.008















Your World, Our World: Resilient Environment and Sustainable Resource Management for All

















CHALLENGES

- The Absence of enough survey control benchmarks from phase 1.
- The controls available were not in proper sync with existing structures.
- Weather conditions posed a challenge.
- Scanty Information available from the Phase I project.













LESSONS LEARNT

Controls should be built to be permanent and visible to avoid destruction.

Protect controls with solid and strong barricades.

Tipple check system to acquire the minimum errors in all survey works.









FIG Working Week 2024 Accra, Ghana

Your World, Our World: Resilient Environment and Sustainable Resource Management for All



Commission 5, TF SDG

TS05F: The Growing Roles & Responsibilities of surveyors as Data

Engineers and Resources Managers

Serving Society for the Benefit of People and Planet

























